

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

15-051-20038-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ellis County, Sec. 10 Twp. 12 Rge. 18 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NW SE

Lease Owner Dreiling & Jennings

Lease Name Baker Well No. #2

Office Address Victoria, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-5 19 67

Application for plugging filed 4-5 19 67

Application for plugging approved 4-5 19 67

Plugging commenced 4-5 19 67

Plugging completed 4-5 19 67

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	134'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rotary mud to a depth of 500' where 1st. plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 125' where 2nd. plug was set using 20 sacks cement. Rotary mud was used to fill hole to a depth of 40' where 3rd. plug was set using 8 sacks cement. Filled Rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

4-11-1967
APR 11 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.

Address Route 2, Victoria, Kansas 67671


STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling (employee of owner) or (owner/proprietor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

Leo F. Dreiling, Route 2, Victoria, Kansas 67671
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of April, 1967



My commission expires September 19, 1970

Joseph A. Hess
Notary Public

15-051-20038-00-00
L. J. DREILING and SONS, Inc.
 VICTORIA, KANSAS

WELL LOG

Company	Dreiling & Jennings Victoria, Kansas	Sec. 10	Twp. 12	Rng. 18
Farm	Baker No. #2	Location	SW NW Se	
Total Depth	3604'	County	Ellis	
Comm.	3-31-67	Elevation:	2193'	K.B.
	Comp. 4-5-67		2190'	D. F.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas		2185'	G. R.
	Casing Record	Cement Record	Production:	D & A
	134' 8 5/8"	100 sacks cement		

Figures Indicate Bottom of Formations.

0'	134'	Top Soil & Clay
134'	973'	Shale
973'	1099'	Sand
1099'	1440'	Shale & Redbed
1440'	1481'	Anhy.
1481'	1503'	Shale
1503'	1725'	Shale & Shells
1725'	1819'	Shale & Lime Streaks
1819'	2005'	Shale
2005'	2130'	Lime & Shale
2130'	2380'	Shale & Lime
2380'	2555'	Shale & Lime
2555'	2890'	Shale & Lime
2890'	3115'	Shale & Lime
3115'	3300'	Shale & Lime
3300'	3355'	Lime
3355'	3408'	Lime & Shale
3408'	3504'	Lime
3504'	3593'	Lime
3993'	3604'	Lime
3604'	T.D.	

RECEIVED
 STATE CONSERVATION COMMISSION
 4-11-1967
 APR 11 1967

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

CONSERVATION DIVISION
 Wichita, Kansas

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Baker #2.

Leo F. Dreiling
 LEO F. DREILING

Subscribed and sworn to before me this 10th day of April 1967.

Joseph A. Hess
 JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970