

15-051-21145-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-21,145

LEASE NAME Deutscher

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line
NW SW SW

SEC. 29 TWP. 12S RGE. 20W (E) or (W)

COUNTY Ellis

Date Well Completed

Plugging Commenced 1-16-87

Plugging Completed 1-21-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS Suite 1000 125 N. Market
Wichita, Kansas 67202

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Hays, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3872'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	202'	none
				4-1/2"	3871'	2600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3400' and 4 sacks cement. Shot casing @2600' and pulled a total of 80 joints of 4-1/2" casing. Plugged surface with 4 hulls, 150 econolite w/3 hulls.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 5th day of February, 19 87

Irene Hoover
Notary Public

My Commission Expires:



FEB 9 1987
2-9-1987
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY A. Scott Ritchie

SEC. 29 T. 12S R. 20W
LOC. NW SW SW

FARM DEUTSCHER NO. 1


RIG. NO. 15

TOTAL DEPTH 3872'

COUNTY Ellis
KANSAS

COMM. 1/22/76

COMP. 1/31/76



CONTRACTOR Murfin Drilling

CASING

20	10
15	8 5/8" @ 202' w/150 SX
12	6
13	5
	4 1/2" @ 3871' w/250 SX

ELEVATION

PRODUCTION Producer

FIGURES INDICATE BOTTOM OF FORMATIONS

- 60 - surf clay & sand
- 180 - shale, sand
- 202 - shale
- 1025 - cmt, shale, sand
- 1265 - sand
- 1553 - shale (redbed)
- 1599 - Anhydrite
- 2765 - shale
- 3245 - shale, lime
- 3558 - lime,
- 3580 - lime, chirt
- 3775 - lime
- 3872 - lime, chirt
- 3872 - TD

STATE OF KANSAS

State of Kansas
 County of Sedgwick

NOTARY PUBLIC
JOLENE S. FRISBIE
Wichita, Kansas

I, Wm. S. Shropshire of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Deutscher #1 well.

Wm. S. Shropshire

Subscribed and sworn to before me this 5th day of February 19 76

JOLENE S. FRISBIE, STATE NOTARY PUBLIC

My Commission Expires: My Comm. Exp. March 13, 1979

Jolene S. Frisbie
NOTARY PUBLIC

