

200 Colorado Derby Building
Wichita, Kansas 67202

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Ginther
WELL NUMBER 1
2310 Ft. from S Section Line
330 Ft. from E Section Line
SEC. 29 TWP. 12 RGE. 20 (E) or (W)
COUNTY Ellis
Date Well Completed 9/79
Plugging Commenced 11/18/92
Plugging Completed 11/18/92

LEASE OPERATOR Diehl Oil, Inc.
ADDRESS P. O. Box 234 Hays, KS 67601
PHONE# (913) 625-6711 OPERATORS LICENSE NO. 09346

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on 11/18/92 (date)
by Marion Schmidt (KCC District Agent's Name).
Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Marmaton Depth to Top 3783 Bottom 3791 T.D. 3850
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put In	Pulled out
		0	260	8-5/8"	260'	-0-
		0	3900	4 1/2"	3900'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Packer & plug stuck in hole @ 2071'. Load hole with water, bypass closed. Run in tubing to stuck tools. Pick up one joint. Pump in 104 sacks 65/35 poz 8% gel. Cement to surface. Pull out tubing. Pump in 15 sacks 65/35 poz 8% gel @ 600#. Shut in 600#. Cut off casing hanger. Weld plate on top of 8-5/8". Test annulus, pump 0 sx @ 600#. NOTE: Perforated 3 holes @ 1555. Used 200# hulls. Plugging complete @ 5:00.


Name of Plugging Contractor B J Services License No. _____
Address 1707 East 10th Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Diehl Oil, Inc. by Glenn Diehl
STATE OF Kansas COUNTY OF Ellis, ss.

RECEIVED
11-20-1992
NOV 20 1992

Glenn D. Diehl (Employee of Operator or Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P. O. Box 234 Hays, KS 67601



SUBSCRIBED AND SWORN TO before me this 19th day of November, 1992

[Signature]
Notary Public

My Commission Expires: 2/5/94
USE ONLY ONE SIDE OF EACH FORM