

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-051-22879-00-00

API NUMBER 15-051-22,879

LEASE NAME Nicholson

WELL NUMBER 2

990 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 29 TWP. 12 RGE. 20 (X or W)

COUNTY Ellis

Date Well Completed 4/9/82

Plugging Commenced 10/2/89

Plugging Completed 10/2/89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Black Diamond Oil, Inc.

ADDRESS 1105 E. 30th Suite A, Hays, Ks. 67601

PHONE#(913) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well Oil & Water

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 29, 1989 (date)

by Don Butcher & Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Marmaton Depth to Top 3785 Bottom 3818 T.D. 3860

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Oil & water	0	250	8 5/8	250	0
		0	3885	4 1/2	3885	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated 1565' & 600'-each with 3 holes. Ran tubing to T.D. Circulated 50  
sks cement to bottom (3860'-3510'.) Pulled tubing to 1588'. Circulated cement  
from 1588' to surface (100 sks cement.) Pulled tubing, tied on to 4 1/2" &  
squeezed with 100 more sacks cement. (Shut in pressure 250#.)  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Ivan Holt Well Servicing License No. \_\_\_\_\_

Address P.O. Box 401, Russell, Ks. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil, Inc

STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Vehige

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kenneth Vehige

Kenneth Vehige

(Address) 1105 E. 30th Suite A, Hays, Ks. 67601

SUBSCRIBED AND SWORN TO before me this 9th day of Oct., 19 89

**Jolene H. Klaus**  
NOTARY PUBLIC  
State of Kansas  
MY APPT. EXPIRES 7/1/90

Jolene H. Klaus Notary Public  
Commission Expires: 2/5/90

25-90