

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31514
Name: Thoroughbred Assoc. LLC
Address 1: 8100 East 22nd St. N. Bldg. 600, Suite F
Address 2: _____
City: Wichita State: KS Zip: 67226
Contact Person: _____
Phone: (316) 685-1512
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: VCCPS SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 5829 Bottom: 5836 T.D. 5952
_____ Depth to Top: 5830 Bottom: 5834 T.D. 5952
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 033-21-272 - 0000
Spot Description: _____
NW SE SE SE Sec. 16 Twp. 18 S. R. 19 East West
585 Feet from North / South Line of Section
585 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Comanche
Lease Name: Big Red Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: 10/7/2009 (Date)
by: Eric MacLaren (KCC District Agent's Name)
Plugging Commenced: 10/9/2009
Plugging Completed: 10/14/2009

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|-------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | | 20" | 90' | none |
| | | | 8 5/8 | 735' | none |
| | | | 5 1/2 | 5945' | 2700' |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bridge plug set at 5070', 2 sacks cement spot with dump bailer, casing load with salt water, cut 5 1/2 casing at 2700' and remove, run 2 3/8 tubing in to 760', spot 12 sacks jell, 50 sacks 60/40 poz, 4% jell, 2nd 300', 50 sacks, 3rd 60' 20 sacks.
10/15 - measure 170' redi mix 4' from surface

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 19 2009

Plugging Contractor License #: 5105 Name: Clarke Corporation
Address 1: P.O. Box 187 Address 2: _____
City: Medicine Lodge State: Kansas Zip: 67104
Phone: (620) 886-5665
Name of Party Responsible for Plugging Fees: Thoroughbred Assoc. LLC
State of Kansas County, Barber ss.

CONSERVATION DIVISION
WICHITA, KS

Mark Morgenstern Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenstern