

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5004
Name: Vincent Oil Corporation
Address 1: 155 N. Market, Suite 700
Address 2: _____
City: Wichita State: Ks Zip: 67202 + 1821
Contact Person: M.L. Korphage
Phone: (316) 262-3573
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. 5040'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 057-20642-00-00
Spot Description: ~SE-NE-SE-NW
SE NE SE NW Sec. 33 Twp. 25 S. R. 24 East West
1,880 Feet from North / South Line of Section
2,520 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ford
Lease Name: Bleumer Well #: 1-33
Date Well Completed: 8/31/2009
The plugging proposal was approved on: 8/28/2009 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 8/31/09
Plugging Completed: 8/31/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface Casing	8 5/8"	442'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole filled with rotary mud, placed cement plugs with drill pipe as follows:

Set 1st plug @ 1560' with 50 sx cement

Set 2nd plug @ 880' with 80 sx cement

Set 3rd plug @ 470' with 50 sx cement

Top Plug @ 60 ft with 20 sx cement

Plugged Rathole with 30 sx cement & Mouse hole with 20 sx cement

Used total of 250 sx 60 / 40 Poz (4% Gel), Allied Cementing Ticket # 043027; Plug Down at 7:30 Am 8/31/2009

RECEIVED
OCT 16 2009
KCC WICHITA

Plugging Contractor License #: 5929 Name: Duke Drilling Co., Inc.
Address 1: P.O. Box 823 Address 2: _____
City: Great Bend State: Kansas Zip: 67530 + _____
Phone: (620) 793-8366

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation (KCC Lic. #5004)

State of Kansas County, Sedgwick, ss.

M.L. Korphage Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: M.L. Korphage

[Handwritten initials]