

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32875
Name: CWB-Co.
Address 1: PO Box 186
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Tom Denning
Phone: (785) 628-2593
Type of Well: (Check one) ☐ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☒ ENHR Permit #: E-25,750 ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-20906-00-02
Spot Description: 15 KCCPKT
C NE SE SW Sec. 34 Twp. 19 S. R. 19 ☐ East ☒ West
982 Feet from ☐ North / ☒ South Line of Section
3,134 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☒ SE ☐ SW
County: Ellis
Lease Name: Doerr Well #: 3
Date Well Completed: 07/06/1973
The plugging proposal was approved on: 08/24/2009 (Date)
by: Pat Staab (KCC District Agent's Name)
Plugging Commenced: 08/24/2009
Plugging Completed: 08/24/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surface	8 5/8"	1252'	none
		production	5 1/2"	3649'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated 5 1/2" casing at 1800', 1250', 550' and 150'. Ran 2" tubing to 2187'. Spot 100 sx. Wait 15 minutes and spot another 150 sx of cement with 400# of hulls. Pulled up to 1200'. Closed backside and mixed another 25 sx at 700#. It held pressure. Released pressure and pulled tubing. Hooked up to the casing with a 5 1/2" swage and mixed 35 sx and cement circulated around annulus. Shut in annulus and pressure casing to 500# and it held 250#.

Plugging Contractor License #: 34266 Name: Allied Cementing Co., LLC
Address 1: PO Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + _____
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: CWB-Co.
State of Kansas County: Ellis ss. _____
Tom Denning (Print Name) ☒ Employee of Operator or ☐ Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tom Denning

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

OCT 15 2009

KCC WICHITA

ALLIED CEMENTING CO., LLC. 037548

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>8-24-09</u>	SEC. <u>14</u>	TWP. <u>15</u>	RANGE <u>19</u>	CALLED OUT	ON LOCATION <u>9:15am</u>	JOB START <u>12:00am</u>	JOB FINISH <u>1:00 am</u>
LEASE <u>Doer</u>	WELL # <u>3</u>	LOCATION <u>Schoenchen Ks. 4w</u>			COUNTY <u>Ellis</u>	STATE <u>KANSAS</u>	
☒ OLD OR NEW (Circle one)		<u>1 S 1w 1/4 X DNTD</u>					

CONTRACTOR Prairie Hawk OWNER _____
TYPE OF JOB Plug Abandoned well
HOLE SIZE _____ T.D. _____
CASING SIZE 5 1/2 DEPTH 3649
TUBING SIZE 2" DEPTH 2187
DRILL PIPE 8 5/8 Surface DEPTH 1252
TOOL _____ DEPTH _____
PRES. MAX 700# MINIMUM 500#
MEAS. LINE _____ SHOE JOINT _____
CEMENT LEFT IN CSG. _____
PERFS @ 1800', 1250', 550', 150'
DISPLACEMENT _____

EQUIPMENT

PUMP TRUCK CEMENTER Gilbert
417 HELPER CRAIG
BULK TRUCK
473 DRIVER Wayne GB
BULK TRUCK
378 DRIVER ALVIN GB

CEMENT
AMOUNT ORDERED 300 SX 6% 4% GEL
400 # Hull's

COMMON	<u>180</u>	@	<u>13.50</u>	<u>2430.00</u>
POZMIX	<u>120</u>	@	<u>7.55</u>	<u>906.00</u>
GEL	<u>10</u>	@	<u>20.25</u>	<u>202.50</u>
CHLORIDE		@		
ASC		@		
<u>Hull's</u>	<u>4</u>	@	<u>31.05</u>	<u>124.20</u>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>300</u>	@	<u>2.25</u>	<u>675.00</u>
MILEAGE	<u>10/16/mi</u>			<u>450.00</u>

REMARKS:

Run 2" Tubing to 2187', Spot 100 SX Neat
Wait 15 min. Spot another 150 SX Cement (Cement circ, to surface)
w/ 400 # Hull's. Pulled up to 1200'
Closed Backside, mixed another 25 SX @
700# (Held) Released & pulled tubing.
Hooked up to CSG w/ 5 1/2 Swaye & 1
mixed 25 SX (and cement circulated
around annulus. Shut in annulus
& pressured CSG to 500# (Held) 250#
THANKS

CHARGE TO: C.W.B. Oil Co.

STREET _____

CITY _____ STATE _____ ZIP _____

*STATE Rep. Pat STAAB
ON Location

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME [Signature]

SIGNATURE _____

PLEASE RETURN EQUIPMENT

RECEIVED

OCT 15 2009

KCC WICHITA

TOTAL _____

SALES TAX (If Any) _____

TOTAL CHARGES [Signature]

DISCOUNT [Signature]

IF PAID IN 30 DAYS