


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-22161-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County County. Sec. 4 Twp. 12S Rge. 19W E/W
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines
SE NE NE

Lease Owner Green Oil Operations
Lease Name SEITZ #1 Well No. 1
Office Address P.O. Box 503, Hays, KS 67601
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry hole
Date Well completed December 6 1980
Application for plugging filed December 6 1980
Application for plugging approved December 6 1980
Plugging commenced December 6 1980
Plugging completed December 6 1980

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3720'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. 3720' RTD

Set 1st Plug @ 700' with 50 sx.

Set 2nd Plug @ 180' with 30 sx.

Set 3rd Plug @ 40' to surface with 10 sx. & 5 sx. in rathole.

All cement 50/50 posmix, 6% gel.

Plug was down @ 10:00 a.m., 12/06/80.

Plugging Supervisor - Marion Schmidt, Hays, KS

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1980

12-17-1980

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this report)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec./Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Jack L. Partridge


801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 1980

My commission expires

8-18-84

Jeanette A. Metheny
Jeanette A. Metheny Notary Public.



15-051-22161-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Green Oil Operations
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: SEITZ #1
 LOCATION: SE NE NE, Section 4-12S-19W
 Ellis County, Kansas
 SPUD DATE: 11/28/80
 COMPLETION DATE: 12/07/80

0	1459	Sand & Shale
1459	1483	Anhydrite
1483	1616	Sand & Shale
1616	2079	Shale & Redbed
2079	2540	Shale & Sand
2540	3720	Lime & Shale
	3720	Rotary Total Depth

Spud @ 8:00 p.m., 11/28/80. Drilled a 260' - 12 1/4" hole. Ran 6 jts. of 8 5/8" - 24# casing (tally 247.37). Set at 255.36. Cemented with 190 sx. of common 2% gel, 3% c.c. Cement did circulate. Plug was down at 3:00 a.m., 11/29/80. Waiting on cement.

RTD 3720'. D & A. 1st Plug @ 700' with 50 sx. 2nd Plug @ 180' with 30 sx. 3rd Plug from 40' to surface with 10 sx. & 5 sx. in rathole. All cement 50/50 posmic, 6% gel. Plug Was down @ 10:00 a.m., 12/06/80. Plugging supervisor - Marion Schmidt, Hays, Kansas.

SAMPLE TOPS:

Anhydrite 1464'
 B/Anhydrite 1495'

RECEIVED
 STATE CORPORATION COMMISSION

DEC 17 1980
 12-17-1980
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SEITZ #1, SE NE NE, Section 4-12S-19W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec./Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 16th day of December, 1980.

Jeanette A. Metheny
 Jeanette A. Metheny, Notary Public

