

HY

API NUMBER 15-051-24,566

15-051-24566-00-00

LEASE NAME Spreen

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

2,310 Ft. from S Section Line

1,650 Ft. from E Section Line

LEASE OPERATOR McNames & Patterson

SEC. 8 TWP. 12 RGE. 19 (E) or (W)

ADDRESS P.O. Box 20058, Wichita, Kansas 67208

COUNTY Ellis

PHONE#(316) 733-5750 OPERATORS LICENSE NO. 8449

Date Well Completed 9-28-88

Character of Well D & A

Plugging Commenced 9-28-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-28-88

The plugging proposal was approved on 9-28-88 (date)

by David Wann (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of _____ water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	NOV 25 1988 10-25-1988 RECEIVED CONSERVATION DIVISION Wichita, Kansas			8 5/8"	233'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill hole w/heavy mud. Push bridge plug to 1,510', pump 25 sax cement down 4 1/2" drill pipe.
Push bridge plug to 810', pump 100 sax cement down 4 1/2" drill pipe. Push bridge plug to 280',
pump 40 sax cement down 4 1/2" drill pipe. Push bridge to 40', dump 10 sax cement on plug to
cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164

Address Shields Bldg., Russell, Kansas 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor
 (Employee of ~~operator~~) or (~~operator~~) of
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. - Trust

(Address) Shields Bldg., Russell, Kansas

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 88

Ruth Phillips
 Notary Public


My Commission Expires: _____



WELL LOG

Operator: McNames & Patterson
Well: Spreen #1
Commenced: September 23, 1988
Completed: September 28, 1988
Contractor: Shields Drilling Co., Inc.

Well Description: NE NW SE
Sec. 8-12S-19W
Ellis Co., Kansas



CASING RECORD		
Size	Run	Pulled
8 5/8"	233'	Cmtd. w/150 sax

Elevation: 2,160' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Surface clay & shale	237'	
Shale	942'	
Shale & sand	1,507'	
Anhydrite	1,550'	
Shale	1,865'	
Shale & lime	3,366'	
Lime	3,443'	RTD

RECEIVED
STATE CORPORATION COMMISSION

10-25-1988
OCT 25 1988

CONSERVATION DIVISION
Wichita, Kansas

Notes