


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 23 Twp. 12 Rge. 20 (E) W (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW'SW" or footage from lines C SE SE
Lease Owner Phillips Petroleum Company
Lease Name Staab "A" Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 11-26-63 19
Application for plugging filed 12-31-63 19
Application for plugging approved 1-2-64 19
Plugging commenced 1-7-64 1-7-64 19
Plugging completed 1-9-64 1-9-64 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 1-3-64 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3962 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300'	None
				4-1/2"	3962'	3089'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

--Checked hole to plug back, sanded hole to 3500' and dumped 3 sacks of cement @ 3500' with dump bailer. Pulled 4 1/2" casing to 575', circulated with 21 sacks of gel mud and 20 sacks of cement. Pulled 4 1/2" casing to 220' and pumped in 20 sacks of cement. Pulled balance of 4 1/2" casing, checked mud to 35' and ran 12 sacks of cement to cap well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
1-20-1964
JAN 20 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of January, 1964

My commission expires May 20, 1964
Milton J. Volin Notary Public.

State

DRILLER'S LOG

COMPANY: Phillips Petroleum Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: STAAB A-#1
 LOCATION: 125' N. or C SE SE
 Sec. 23-12S-20W, ELLIS CO., KS.
 COMMENCED: 10-21-63
 COMPLETED: 11-1-63

0	65	Clay and Sand Streaks
65	750	Shale
750	1575	Shale and Shells
1575	1617	Anhydrite
1617	1900	Shale and Shells
1900	2465	Shale with Lime
2465	2610	Lime
2610	2985	Lime with Shale
2985	3069	Shale and Lime
3069	3390	Lime and Shale
3390	3934	Lime (Arbuckle @ 3915')
3934	3965	Arbuckle
	<u>3965</u>	<u>Rotary Total Depth - Set 4 1/2"</u>

STATE CORPORATION COMMISSION
 1-20-1964
 JAN 20 1964
 CONSERVATION DIVISION
 Wichita, Kansas


Set 8 5/8" Surface Casing @ 299.76' with landing joint. Cemented with 100 sacks Common, 20% Diacel D and 200# c.c. and 50 sacks Common with 100# c.c.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Staab A-#1 located 125' North of C SE SE of Section 23, Township 12 South, Range 20 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
 COUNTY OF BARTON) SS

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 4th day of November, 1963.



Ulanda Nichols
 Ulanda Nichols, Notary Public

My Commission Expires:
 April 1, 1967