

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-24531-00-00

API NUMBER 15-051-24531

LEASE NAME Armbrister

WELL NUMBER 1

SPOT LOCATION NE SW SE

SEC. 22 TWP. 12 RGE. 20 (XXX) (W)

COUNTY Ellis

Date Well Completed 11-12-1987

Plugging Commenced 11-12-1987

Plugging Completed 11-12-1987

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Staab Oil/Ash-Bie Oil

ADDRESS Box 194 Ellis, Kansas 67637

PHONE # (913) 726-3663 OPERATORS LICENSE NO. _____

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3905'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	218	8 5/8"	218	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
1st Plug set at 1600' with 20 sacks cement, 60/40 poz 6% Gel;
2nd plug set at 900' with 100 sacks cement, 60/40 poz 6% Gel and 1 sack cello flake;
3rd plug set at 250' with 40 sacks cement, 60/40 poz 6% Gel;
4th plug set at 40' with 10 sacks cement, 60/40 poz 6% Gel;
10 sacks in rat hole.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ-Titan License No. _____
Address Hays, Kansas 67601

STATE OF Kansas COUNTY OF Graham, ss.

Jerry M. Helberg (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



RECEIVED
STATE CORPORATION COMMISSION
12-8-1987
DEC 8 1987

(Signature) Jerry M. Helberg
(Address) Box 32, Morland, Kansas 67650

SUBSCRIBED AND SWORN TO before me this 16th day of Dec, 1987
CONSERVATION DIVISION
Wichita, Kansas
Coleen Shields
Notary Public

My Commission expires: March 11, 1990