


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

_____ ELLIS _____ County. Sec. 26 Twp. 12 Rge. 20 (E) W (W)
Location as "NE/CNW/SW" or footage from lines _____ C SW NE
Lease Owner _____ Harms Petroleum Company
Lease Name _____ KING _____ Well No. 1
Office Address _____ P.O. Box 488 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____ Dry Hole
Date well completed _____ April 9 19 67
Application for plugging filed _____ April 9 19 67
Application for plugging approved _____ April 9 (verbally) 19 67
Plugging commenced _____ April 9 19 67
Plugging completed _____ April 9 19 67
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____ Yes

Name of Conservation Agent who supervised plugging of this well _____ Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3972 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	200'	8 5/8"	200'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from total depth to 550 feet

with plug and 20 sacks of cement at this point. Heavy mud to 190 feet

with plug and 20 sacks of cement at this point. Heavy mud to 40 feet

with plug and 8 sacks of cement at this point.

RECEIVED
KANSAS STATE CORPORATION COMMISSION
STATE CORP.
5-8-1967
MAY 8 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____ Harms Drilling Company
Address _____ P.O. Box 488 Great Bend, Kansas 67530


STATE OF _____ KANSAS _____, COUNTY OF _____ BARTON _____, ss.
_____ ALLAN HARMS _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
P.O. Box 488 Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this _____ 6th _____ day of _____ May _____, 19 67

Helen E. Gearhart
Notary Public.

My commission expires _____ January 22, 1970



DRILLERS LOG

COMPANY: HARMS PETROLEUM COMPANY
FARM: KING #1
COMMENCED: March 31, 1967

C SW NE Section 26-12-20W
Ellis County, Kansas
COMPLETED: April 9, 1967

ELEVATION: 2215 KB

0 - 200	shale
200 - 710	shale & sand
710 - 930	red bed
930 - 1085	shale
1085 - 1340	sand & shale
1340 - 1586	shale & red bed
1586 - 1630	anhydrite
1630 - 2130	shale & shells
2130 - 2480	shale & lime
2480 - 2760	lime & shale
2760 - 2890	shale & lime
2890 - 3000	lime & shale
3000 - 3210	shale & lime
3210 - 3440	lime & shale
3440 - 3520	shale & lime
3520 - 3959	lime
3959 - 3972	dolomite
3972	Total depth

RECEIVED
STATE CORPORATION COMMISSION
5-8-1967
MAY 8 1967
CONSERVATION DIVISION
Wichita, Kansas

SET 200 feet of 8 5/8 inch.

CEMENTED with 150 sacks of cement.

TOPS:	ANHYDRITE	-	1586
	TOPEKA	-	3279
	HEEBNER	-	3516
	LANSING	-	3556
	CHERTY CONGLOMERATE	-	3872
	ARBUCKLE	-	3959

DRY, PLUGGED and ABANDONED.

A F F I D A V I T

STATE OF KANSAS)
) SS
COUNTY OF BARTON

I, Allan Harms of the Harms Drilling Company being first duly sworn on oath state:
I have knowledge of the facts, statements and matters herein contained and the
same are true and correct.

Allan Harms
Allan Harms

Subscribed and sworn to before me this 6th day of May, 1967.

Helen E. Gearhart
Helen E. Gearhart - Notary Public

My commission expires: January 22, 1970

