

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-051-23,418

LEASE NAME Armbrister

WELL NUMBER 1

SPOT LOCATION SW NW NE

SEC. 27 TWP. 12 RGE. 20 (X) OR (W)

COUNTY Ellis

DATE WELL COMPLETED 4-30-83

PLUGGING COMMENCED 12-14-84

PLUGGING COMPLETED 12-14-84

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Quinn Oil Production, Inc.

ADDRESS 1811 East 24th St.

PHONE # (913) 625-7106 OPERATORS LICENSE NO. 5226

CHARACTER OF WELL Oil
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays, Marion Schmidt

IS ACC-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION Marmaton DEPTH TO TOP 3810 BOTTOM 3846 T.D. 3900

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	249	8-5/8"	249	0
				5 1/2"	3887	0

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Pump 20 sx down annulus, cement circulated, shut down. Pump down 5 1/2" casing 50 sx cement with 3 sx hulls, 17 sx gel spacer, 20 sx cement, 5 sx gel spacer, stop gel, drop plug, cement with 100 sx. Cement was 50/50 Poz mix, 6% gel, 3% CaCl2

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Dowell
ADDRESS 905 East 9th P.O. Box 219, Hays, KS 67601

LICENSE No. _____



STATE OF KANSAS COUNTY OF ELLIS, SS.

Glenn D. Diehl (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Glenn D. Diehl
(ADDRESS) 1811 East 24 Hays

SUBSCRIBED AND SWORN TO BEFORE ME THIS 2nd DAY OF JANUARY, 1985



Kay Lynn Philip
NOTARY PUBLIC

MY COMMISSION EXPIRES: 4-6-87