


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec 27 Twp. 12S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NE
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name Armbrister Well No. 1
Office Address 800 Bitting Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed April 17, 1963 19
Application for plugging filed April 17, 1963 19
Application for plugging approved April 17, 1963 19
Plugging commenced April 17, 1963 19
Plugging completed April 17, 1963 10 A. M. 19
Reason for abandonment of well or producing formation non-productive
in commercial quantities
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3910 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	163'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

No. 1 Plug at 550 feet with 20 sacks cement
No. 2 plug at 160 feet with 20 sacks cement
No. 3 plug at 40 feet with 10 sacks cement
Heavy mud between each plug - 2 sacks cement
in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
5-3-1963
MAY 3 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton and Quaker Drilling Company
Address 800 Bitting Building, Wichita, Kansas (Quaker)

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul

800 Bitting Building, Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 63

My commission expires August 10, 1965

[Signature]
Notary Public.

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: April 6, 1963

Contractor: Quaker Drilling Co., Inc.

Completed: April 17, 1963

Alpine's No. 1 Armbrister
NW NE Sec. 27-12S-20W
Ellis County, Kansas

Elevation: 2194 K. B.

Casing Record

Set 8 5/8 inch casing at 163 feet with 140 sacks cement

(Figures Indicate the Bottom of The Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Post Rock and Blue Shale	163	Heebner	3481 -1287
Shale and Sand	600	Toronto	3501 -1307
Shale	1060	Lansing	3521 -1327
Sand	1280	Base of Kansas City	3770 -1576
Red Bed	1415	Conglomerate	3813 -1619
Shale, Shells with Pyrite	1574	Arbuckle	3890 -1696
Anhydrite	1620	Rotary Total Depth	3910 -1716
Shale and Shells	2195		
Lime and Shale	3380		
Lime	3490		
Lime and Chert	3545		
Lime	3635		
Cherty Lime and Shale	3690		
Lime	3740		
Cherty Lime and Shale	3910		

RECEIVED
STATE CORPORATION COMMISSION5-3-1963
MAY 3 1963CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NW NE of Section 27, Township 12 South, Range 20 West, Ellis County, Kansas.

QUAKER DRILLING CO., INC.

By: 

Thomas M. McCaul

SUBSCRIBED AND SWORN TO before me a Notary Public this 22nd day of April 1963.


Virginia Mundell, Notary PublicMY COMMISSION EXPIRES:
August 10, 1965