

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 1200
Wichita, Kansas 67202

RECEIVED
12-15-2000
DEC 15 2000

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-195-00361-00-02

API NUMBER 15-195-00361-00-02

LEASE NAME Kohl

WELL NUMBER #8

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 2 TWP. 12 RGE 21 (E) or (W)

COUNT Trego

Date Well Completed 11/1963

Plugging Commenced 11/29/2000

Plugging Completed 11/29/2000

CONSERVATION DIVISION
Wichita, Kansas

LEASE OPERATOR Benchmark Oil and Gas Corporation

ADDRESS 1515 Arapahoe St., Suite 580 Denver, CO 80202

PHONE # (303) 595-9251

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 17, 2000 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3974' Bottom 4035' T.D. 4035'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Arbuckle</u>	<u>Oil</u>	<u>3974'</u>	<u>4035'</u>	<u>5-1/2"</u>		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Dug workover pit and installed liner. Dug out casing head and piped the surface casing to the top of the ground. Moved 77 joints of tubing to location. Rigged up Fischer Well Service and ran 75 joints of tubing in well. End of tubing is at 2340'. Hooked up Allied Cementing trucks to tubing and pumped 100 sks of 60/40 pos cement with 550 #'s of hauls down tubing. Pulled 20 joints of tubing out of well and pumped 100 sks of cement with 150#'s of hauls at 1540' Pulled 18 joints of tubing and pumped 110 sks of cement down tubing at 982' and circulated cement to surface. Pulled all of the tubing out of well and filled casing with 65 sks of cement. ISIP 300#'s. Hooked up to the surface casing and pressured the casing to 400#'s and it held. Rigged down unit. Cut off casing below ground and backfilled pit.

Name of Plugging Contractor Benchmark Oil and Gas Corporation License No. 31566

Address 1515 Arapahoe St., Suite 580 Denver, CO 80202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Benchmark Oil and Gas Corporation

STATE OF Colorado COUNTY OF Denver, ss.

Cindy A. Tokarchik for Benchmark Oil and Gas Corporation (Employee of Operator) or (Operator) or above-described well, being first duly sworn on oath; says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Cindy A. Tokarchik Production Coordinator

(Address) 1515 Arapahoe St., Suite 580 Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 11th day of December, 20 00

Veranda M. Stewart

Notary Public

My Commission Expires

My Commission Expires:

03/11/2002

MB