

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-195-21718-00-00

API NUMBER 15-195-21,778

LEASE NAME Deutscher "E"

WELL NUMBER #1

SPOT LOCATION NW SW NE

SEC. 4 TWP. 12 RGE. 21 (W)

COUNTY Trego

Date Well Completed 1-22-86

Plugging Commenced 2-18-86

Plugging Completed 2-18-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum, Inc.

ADDRESS P.O. Box 1447, Great Bend, KS 67530

PHONE # (316) 793-8471 OPERATORS LICENSE NO. 5238

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays District #6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation NA Depth to top _____ bottom T.D. 4060'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	216'	0
				7 7/8"	4058'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Allied Cementing plugged well as follows: Pumped 25 sax 60/40 Poz mix; 6% gel, 1 sack hulls, pumped 24 sax gel w/2 sax hulls; Release wiper plug. Pumped 125 sax 60/40 Poz mix, 6% gel. Pumped 50 sax 60/40 Poz mix down backside w/2 sax hulls. Cementing press. 200#; S.T. 100#; Witnessed by State man Dennis Hamel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum, Inc. License No. 5238
Address P.O. Box 1447, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Monte Chadd


(employee of operator) or
X ~~CODED COPY~~ of above-described well, being duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed at the same are true and
correct, so help me God.

MAR 5 1986
3-5-1986
CONSERVATION DIVISION
Wichita, Kansas

(Signature) Monte Chadd

(Address) P.O. Box 1447, Great Bend, KS 67530

SUBSCRIBED AND SWORN JUAN D. MUNZ me this 28 day of February, 19 86



Juan D. Munz
Notary Public

My Commission expires: 11-09-88

Juan D. Munz