

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

Re: 15-195-21-00-00

API NUMBER 15-195-21, 021

LEASE NAME Walz 'F'

WELL NUMBER 2

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 4 TWP. 12 RGE. 21 (E) or (W)

COUNTY Trego

Date Well Completed 7/82

Plugging Commenced 10-7-93

Plugging Completed 10-7-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum, Inc.

ADDRESS 301 N. Main, Suite 900 Wichita, KS 67202

PHONE# (316) 291-8282 OPERATORS LICENSE NO. 5238

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 7, 1993 (date)

by Hubert Deines (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached?

Producing Formation Marmaton Depth to Top 3922 Bottom 3936 T.D. 4033

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	755	None.
				5 1/2"	4032	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
Perf. 2 holes at 2470', 1820' and 960', pumped 50 sx 60/40 poz. 10% gel down Annulus mp 700#. S.I. 500#. Pumped 275 sx 60/40 poz, 10% gel and 300# hulls down 5 1/2" csg. MP 500#. S.I. 500#

Name of Plugging Contractor Allied Cementing Co.

License No.

Address P. O. Box 420, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum, Inc.


STATE OF Kansa COUNTY OF Sedgwick, ss.

Paul Kreutzer

(Employee of Operator or Operator) c above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature)

(Address) 301 N. Main, Suite 900 Wichita, KS 67202 Wichita, Kansas



SWORN TO before me this 26 day of October, 19 93

Sherry Fraser
Notary Public

3-20-94

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1993
10-27-1993
REGISTRATION DIVISION

Schlumberger

COMPENSATED SONIC/GR

CSU

COMPANY: PETROLEUM, INC.

WELL: #2 WALZ "F"

FIELD: KOHL WEST

COUNTY: TREGO

STATE: KANSAS

LOCATION: SW NE SE

SEC: 4

TWP: 12S

RGE: 21W

PERMANENT DATUM: GROUND LEVEL ELEVATIONS-
 ELEV. OF PERM. DATUM: 2313.0' KB: 2318.0'
 LOG MEASURED FROM: KELLY BUSHI DF: 2315.0'
 5.0' ABOVE PERM. DATUM GL: 2313.0'
 DRLG. MEASURED FROM: KELLY BUSHING

DATE: 28 JUL 1982
 RUN NO: 1

DEPTH-DRILLER: 4033.0'
 DEPTH-LOGGER: 4032.0'
 BTM. LOG INTERVAL: 4000.0'
 TOP LOG INTERVAL: 758.0'

CASING-DRILLER: 755'
 CASING-LOGGER: 758'
 CASING: 8 5/8

BIT SIZE: 7 7/8

RECEIVED
 RECEIVED
 STATE CORPORATION COMMISSION
 JUN 6 1982
 JUN 6 1993
 GREAT BEND
 Division of CONSERVATION DIVISION
 Wichita, Kansas