


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 2 Twp. 12 Rge. 21 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines. SW - SW - SE

Lease Owner Glickman Oil Co.

Lease Name Horton Well No. 1

Office Address Wichita, Kansas, P. O. Box 3104

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed July 12 1963

Application for plugging filed October 28 1963

Application for plugging approved October 28 1963

Plugging commenced Oct. 25 1963

Plugging completed Nov. 2 1963

Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production Sept. 26 1963

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4068 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	188'	None
				7"	4015'	3686.60'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4068 feet to surface feet for each plug set.

Sanded up to 4000' dump 5 sacks of cement on bottom. Pulled pipe up 600' circ. with mud, pump 30 sacks of cement to 600'. Pulled pipe up to 200' pump 30 sacks of cement, pulled pipe out put 10 sacks of cement on top. Well completed.

RECEIVED
STATE CORPORATION COMMISSION
11-8-1963
NOV 8 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.

Address P.O. Box 313 Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Milton Glickman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Milton Glickman Partner

P. O. Box 3104, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of November, 19 63



November 19, 1963

Lorella Schauf Notary Public.

GLICKMAN OIL COMPANY

P. O. Box 3108 3104

Wichita, Kansas

DRILLERS WELL LOG

Company: Glickman Oil Company

Location: SW SW SE

Farm: Horton

Well No. 1

Section 2-12S-21W

Trego County, Kansas

Commenced: July 1, 1963

Elevation: 2318 K.B.

Completed: July 13, 1963

Total Depth: 4028'

Geologist: Max S. Houston

Casing: 10-3/4" @ 188' w/100 sx.
7" @ 4015' w/50 sxs.

Production:

Figures Indicate Bottom of Formations

35	Surface Clay & Lime		
190	Sand		
830	Shale		
1235	Shale & Clay	TOPS	
1742	Shale & Shells		
1799	Anhydrite	Topeka	3369
1945	Shale & Shells	Heebner	3590
2115	Shale & Shells Lime	Toronto	3611
2505	Shale & Lime	Lansing	3624
3175	Lime & Shale	Marmaton	3924
3310	Shale & Lime	Conglomerate	3964
3435	Lime & Shale	Weathered Arbuckle	3983
3580	Lime	Solid Arbuckle	4006
3645	Lime & Shale		
3935	Lime		
3995	Lime & Cherty Conglomerate		
4028	Arbuckle		
4028	RTD		

STATE OF KANSAS
NOV 8 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Milton Glickman, of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Horton #1

Milton Glickman

Milton Glickman

Partner

Subscribed and sworn to before me this 17th day of July, 1963

Lorella Schauf

Lorella Schauf

Notary Public

My Commission Expires: November 19, 1963.

