

15-051-21492-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
6-5-1978  
JUN 05 1978

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 051 - 21,492

CONSERVATION DIVISION  
Wichita, Kansas  
(of this well)

Operator's Full Name D-G Oil Operations  
Complete Address Box 503, Hays, Kansas  
Lease Name Adcock Well No. 2  
Location C S/2 NW/4 Sec. 15 Twp. 12 Rge. (E) (W) 18  
County Ellis Total Depth 3771'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX  
Other well as hereafter indicated       
Plugging Contractor Revlin Drlg.  
Address Russell, Kansas License No.       
Operation Completed: Hour 10 P Day 2 Month 6 Year 1978

The above well was plugged as follows:

RTD 3771' 8 5/8 csg. set 214' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.  
Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey  
Well Plugging Supervisor

DATE 6-6-78

WELL NO. 7432-W