

15-051-05124-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-6-1960
JUL 6 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: SE SW NW Sec. 15 Twp. 12 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3714

I have this date completed supervision of plugging of:

Lease Name: Baker Well No. 1

Operator's Full Name: C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kans

Plugging Contractor: Ace Pipe Pulling Co & Globe Cementing Co

Address: Great Bend, Kans License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 27 Month 6 Year 60

The above well was plugged as follows:

8 5/8" 190' circulated with cement - 5 1/2" 3714' with 175 sax cement - Perforated
1478' and squeezed and circulated to 0' with cement 400 sax cement with 25 sax
strata crete - perforated 3350' - Baker plug at 3390'.

Filled with sand to 3330', set 4 sax cement with dump bailer - shot pipe at 500'
pumped hole full heavy mud (20 sax gel), pumped cementing plug on top mud,
followed by 75 sax cement at 600# pump pressure - no pipe recovery.

Mudding and cementing by Globe Cementing Co.

Signed: Jewel P. Kelly
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 7-7-60
INV. NO. 1610-W