

15-051-22088-00-00

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

FORM CP-3
Rev. 6-4-88
RECEIVED
STATE CORPORATION COMMISSION

10-31-1980
OCT 31 1980

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 051-22,088 (of this well)

Operator's Full Name MAI OIL OPERATIONS
Complete Address BOX 33 - RUSSELL, KANS. 67665
Lease Name MASSIER Well No. #1
Location NW-SW-SE Sec. 6 Twp. 12 Rge. 19 (E) (W) W
County ELLIS Total Depth 3791 EF
Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereafter indicated
Plugging Contractor LAWBANCO DRILLING
Address BOX 289 NATOMA, KS. License No.
Operation Completed: Hour 9:00 ^{PM} Day 29 Month OCT Year 1980

The Above well was plugged as follows:

8 5/8" 334 EF SP. CUK w/175 SE QUICK SET. ELV. 2191 K.B.
ORDERED - 105 SE 50/50 POZMIX 6% GEL. + 8 5/8" PLUG.
SPOTTED WITH DRILL STEM. - WITH HEAVY MUD BETWEEN ALL PLUGS.
1 SE PLUG. @ 650 EF w/60 SE CMT.
2ND PLUG. @ 330 EF w/30 SE CMT.
3RD PLUG - SOLID BRIDGE HALL'S - PLUG. @ 40 EF to 0 w/10 SE CMT.
5 SE IN RAT HOLE.

INVOICED

CEMENTED BY ALLIED CMT.

I hereby certify that the above well was plugged as herein stated.

DATE 11-1-1980

INV. NO. 5556-W

Signed: M. J. Schmidt

Well Plugging Supervisor D.R.