

15-051-22898-00-00

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,898

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Full Circle Energy Co.

Complete Address 400 N. Woodlawn, Suite 201, Wichita, Ks. 67208

Lease Name Massier Well No. 1

Location NW NE SW Sec. 8 Twp. 12 Rge. 19 (East) (West)

County Ellis Total Depth 3775'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Co.

Address 1720 K.S.B.B. Wichita, Ks. 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 9:45 PM Day: 28 Month: 6 Year: 19 82

Plugging Operations attended by Agent?: All  Part  None XXX

The above well was plugged as follows:

8 5/8"-220' S.P. cuc. w/165 sacks common-2% Gel.-3% Cal.Cl.

Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug

spot w/drill stem w/heavy mud between all plugs.

1st plug @ 870' w/80 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement

Circulate 10 sacks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1982  
7-1-1982  
CONSERVATION DIVISION  
Wichita, Kansas

Amount of Surface Casing: 220' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

Signed: \_\_\_\_\_  
Conservation Division Agent

DATE 7-1-82  
INV. NO. 560-w