

15-163-00890-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*AL*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company  
Complete Address 2915 N. Lincoln Oklahoma City, Oklahoma 73105  
Lease Name Sutor Well No. 6  
Location NW SW SE Sec. 22 Twp. 10 Rge. (E) (W) 20  
County Rooks Total Depth 3755'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Co. Tools by HOWCO.  
Address \_\_\_\_\_ License No. \_\_\_\_\_  
Operation Completed: Hour 3:15 P Day 10 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 3755' 8 5/8 csg set at 193' cwc 150 sk.  
5 1/2 csg set at 3754' cw 150 sk cmt.  
No pipe recovered.  
Ran 115 jts tbg set at 3450' -pumped 100 lbs hulls -30 sk gel & water -displaced  
25 sk "Halib.-light" cmt. Pulled 94 jts tbg set at 640' & circulated 50 sk cmt to  
surface. Pulled remaining 21 jts tbg & capped 5 1/2 csg with 15 sk cmt.  
Pumped 50 sk cmt down annulus-(5 1/2 X 8 5/8) with 800 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. F. Messing  
Well Plugging Supervisor

INVOICED  
DATE 8/11/72  
INV. NO. 6153-4