

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-185-02077-00-02  
 Spot: SENWSE Sec/Twnshp/Rge: 30-22S-11W  
1650 feet from S Section Line, 1661 feet from E Section Line  
 Lease Name: KOMAREK Well #: 3  
 County: STAFFORD Total Vertical Depth: 3569 feet

Operator License No.: 32432  
 Op Name: LA VETA OIL & GAS, LLC  
 Address: 312 N. BUFFALO  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2800		
CIBP		3502		115.99
SURF	13	216		WITH 220 SX CMT
	11 8.625	2736		WITH 100 SX CMT
PROD	7	3542	2400	WITH 100 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2009 8:30 AM  
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
 Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: BAIL 2 SX CMT ON TOP OF PLUG. PULL 7". PERFORATE 8 5/8" @ 600' RUN TBG TO 600'. CIRCULATE CMT UP 8 5/8" & 13". PULL TBG & TOP OFF BOTH STRINGS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
 Date/Time Plugging Completed: 10/02/2009 9:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

BAILED 2 SX CMT ON TOP OF EXISTING CIBP @ 2800'. PERFORATED 8 5/8" @ 600'. RAN TBG TO 600'. PUMPED 200 SX CMT DOWN TBG CIRCULATING CMT UP THE 8 5/8". PULLED TBG. PUMPED DOWN 8 5/8" WITH 265 SX CMT CIRCULATING UP 13" X 8 5/8" ANNULUS. LOST CIRCULATION. SDON. 10/2/09: TAGGED CMT INSIDE 8 5/8" @ 130' WITH 1" TBG. PUMPED 60 SX CMT FILLING IT TO SURFACE. TAGGED CMT INSIDE 13" X 8 5/8" WITH 1" TBG. PUMPED 40 SX CMT FILLING IT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3542	3569	OH	
3312	3322		

RECEIVED  
 OCT 08 2009  
 KCC WICHITA

INVOICED  
 DATE 11-13-09  
 INV. NO. 2010060489

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

Signed Richard W. Lacey  
 (TECHNICIAN)

RECEIVED  
 OCT - 2 2009  
 KCC DODGE CITY