

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02107-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 31-22S-11W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HEYEN Well #: 1B
County: STAFFORD Total Vertical Depth: 3530 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 312 N. BUFFALO
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13	220		WITH 250 SX CMT
PLG	7	3460		114.73
PROD	7	3518	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2009 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM TO 3240' & 7 SX CMT. RUN BOND LOG & DECIDE REST OF PLUG.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 09/28/2009 4:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3220' & DUMPED 7 SX CMT WITH DUMP BAILER. RAN BOND LOG: LOG INDICATED CMT FROM 0' TO 230' & 380' TO 720'. RAN TBG TO 600' & PUMPED 125 SX CMT CIRCULATING CMT TO SURFACE. PULLED TBG & TOPPED OFF 7" WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3518	3530		

INVOICED
DATE 11-13-09
INV. NO. 2010060489

RECEIVED
OCT 08 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
OCT - 2 2009
KCC DODGE CITY