

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22645-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 26-8S-22W
330 feet from S Section Line, 4800 feet from E Section Line
Lease Name: KIRKPATRICK Well #: 1
County: GRAHAM Total Vertical Depth: 3795 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211	0	150 SX
PROD	4.5	3827	0	175 (PC @ 1739' W/ 375 SX)

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/02/2009 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOHN NEIERNBERGER Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Port collar 1739' w/375 sxs.

123.34

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2009 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3630' - pumped 50 sxs cement with 150# hulls.
Pulled tubing to 3000' - pumped 100 sxs cement with 100# hulls.
Pulled tubing to 1600' - pumped 40 sxs cement to circulate cement.
Pulled tubing out - filled casing down - top full with 15 sxs cement.
Tied onto backside - full.
Max. P.S.I. 100#. Shut in.

Perfs:

Top	Bot	Thru	Comments
3605	3606		
3520	3521		
3475	3476		

RECEIVED
OCT 06 2009
KCC WICHITA
INVOICED
DATE 11-13-09

Remarks: ALLIED CEMENTING COMPANY-TICKET #38543.

INV. NO. 2010060495

Plugged through: TBG

District: 04

Signed Marvin Mills
(TECHNICIAN)

STATE: KANSAS COUNTY: GRAHAM REISSUE 26-8S-22W
FIELD: MICKLESON SOUTHEAST 1/4 MI N PROD (LANSING) SW SW SW
OPER: RITCHIE EXPL 330 FSL 4800 FEL SEC
WELL: 1 KIRKPATRICK WELL CLASS: WOE ELEV: 2200 KB
API: 15-065-22645 STATUS: OIL 2195 GR
SPUD: 07/18/91 COMP: 08/20/91
DTD: 3830 LTD: 3829 FTD: ARBUCKLE PBTD:

LOC: 3 1/2 MI SW BOGUE, KS

IP: COMP 8/20/91, IPP 35 BO, 89 BWPD PROD ZONE- LANSING-KANSAS CITY
3475-3606(GROSS)
NO CORES, SIX DSTS (LANSING-KANSAS CITY EXTENSION)

LOG TOPS:

STONE CORRAL	1772 428	LANSING	3441 -1241
B/ STONE CORRAL	1806 394	B/ KANSAS CITY	3647 -1447
TOPEKA	3184 -984	MARMATON	3683 -1483
HEEBNER	3401 -1201	ARBUCKLE	3772 -1572
TORONTO	3426 -1226	ARBUCKLE	3806 -1606
TD	3830 -1630		

LOG TYPES NOT RPTD
CSGS: 8 5/8 @ 211 W/150 SX,

(OVER)

COPYRIGHT 1992 PETROLEUM INFORMATION CORPORATION

DATE 11/13/92 CARD #00031-KS