

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20625-00-00
Spot: N2N2SE Sec/Twnshp/Rge: 27-8S-26W
3080 feet from N Section Line, 1320 feet from E Section Line
Lease Name: ROBBEN P Well #: 5
County: SHERIDAN Total Vertical Depth: 4010 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220	0	200 SX
T1	2	3966		130.33
PROD	4.5	4009	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2009 3:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOHN NIERNBERGER Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 550 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2009 9:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 220' w/200 sxs cement.
4 1/2" production casing set at 4009' w/200 sxs cement.
TD 4010'. PBTD 3974'. Andydrite depth 2197' - 2230'.
Production casing in poor condition.
Perforated production casing at 2270' - 1370' - 210'.
Ran tubing to 3950' - pumped 150 sxs cement mixed with 250# hulls.
Pulled tubing to 1800' - pumped 290 sxs cement with 250# hulls.
Cement to surface. Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 50 sxs cement.
Connected to 8 5/8" surface casing - pumped 40 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3918	3922		
3898	3902		
3858	3866		
3808	3812		
3766	3770		

INVOICED
DATE 11-13-09
INV. NO. 2010060495

RECEIVED
OCT 08 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #33392.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

