

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22626-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 24-15S-24W  
950 feet from S Section Line, 1545 feet from W Section Line  
Lease Name: LUTTERS Well #: 2  
County: TREGO Total Vertical Depth: 4380 feet

Operator License No.: 34229  
Op Name: S&W OIL & GAS LLC  
Address: 3540 W DOUGLAS, STE 3  
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

142.35

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2009 5:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE  
Date/Time Plugging Completed: 10/02/2009 7:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:  
1st. Plug at 1720' w/25 sxs.  
2nd. Plug at 715' w/100 sxs.  
3rd. Plug at 270' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.

Perfs:  
  
RECEIVED  
OCT 08 2009  
KCC WICHITA  
INVOICED  
DATE 11-13-09  
INV. NO. 2010060496

Remarks: QUALITY OILWELL CEMENTING COMPANY.  
Plugged through: DP

District: 04 Signed [Signature] (TECHNICIAN) CM