

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-28973-00-00
Spot: SWNWSENE Sec/Twnshp/Rge: 22-23S-18E
3465 feet from S Section Line, 1155 feet from E Section Line
Lease Name: DRAKE Well #: 11
County: ALLEN Total Vertical Depth: 1000 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.5	20	0	
PROD	2.875	1000	0	

35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2009 1:00 PM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: BERNIE RUCKERS Company: SOUTHERN STAR CENTEAL GAS P Phone: (316) 685-6908

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO 1000' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2009 4:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE CASING TO 847'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURACE. THE 1" PIPE WAS REMOVED. THE WELL WAS THEN SHUT IN, SQUEEZED TO 550PSI AND SHUT IN.

RECEIVED
KCC DISTRICT #3
SEP 29 2009 CPT
CHANUTE, KS

Perfs:

INVOICED
DATE 11-13-09
INV. NO. 2010060498

RECEIVED
OCT 06 2009
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PCT