

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-23541-00-00  
Spot: E2W2W2SW Sec/Twnshp/Rge: 24-24S-21E  
1320 feet from S Section Line, 336 feet from W Section Line  
Lease Name: RHOTON Well #: 1  
County: BOURBON Total Vertical Depth: 646 feet

Operator License No.: 32711  
Op Name: BECKER, MIKE  
Address: 15135 BROADMOOR  
STANLEY, KS 66223

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	20		

35.00

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2009 8:00 AM  
Plug Co. License No.: 32711 Plug Co. Name: BECKER, MIKE  
Proposal Rcvd. from: MIKE BECKER Company: BECKER, MIKE Phone: (913) 533-2487

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 646'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 546', AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/22/2009 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE WELL TO 646'. 12 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO 646'. THE PIPE WAS PULLED TO 546' AND 12 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFCE.

Perfs:

INVOICED  
DATE 11-13-09  
INV. NO. 2010060481

RECEIVED  
KCC DISTRICT #3  
SEP 30 2009 CPT  
CHANUTE, KS

RECEIVED  
OCT 06 2009  
KCC WICHITA

Remarks:

Plugged through:

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

PJT