

15-051-21759-00-00
11-18

94
R

4-071017

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-21,759
NE NE SE /4 SEC. 29 , 12 S , 20 W
2310 feet from S section line
330 feet from E section line

Operator license# 09346 Lease Ginther well # 1

Operator: Diehl Oil, Inc. County Ellis

Address: P.O. Box 234 Well total depth 3900 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Glenn D. Diehl Surface pipe 8 5/8 Inch @ 260 feet

126.75

Aband. oil well X , Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services - Paul's Well Service License#

Address: Hays, Kansas 67601 - Ellis, Kansas 67637

Company to plug at: Hour: P.M. Day: 18 Month: November Year: 92

Plugging proposal received from: Glenn D. Diehl

Company: Diehl Oil, Inc. Phone: 913-625-6711

Were: 8 5/8" - 260' S.P. cwc w/100 sx. cement. 4 1/2" casing @ 3899'
w/150 sx. cement. Casing squeezed @ 996' w/400 sx. cement - cement
circulated to surface. Perf's 3865' - 3682'. Bridge plug @ 3850'.
K.C. not treated. Packer stuck @ 2071' - could not recover.
Proposal 275 sx. 65/35 pozmix - 8% gel. and 5 sx. hulls. Spot and
displace with tubing - load both 4 1/2" casing and 4 1/2" x 8 5/8"
annulus with cement - shut in under pressure. Perf. @ 1555'.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 5:00P.M. , Day: 18 , Month: November , Year: 92

Actual plugging report: Diehl Oil Inc. ordered 275 sx. 65/35 pozmix -
8% gel. and 5 sx. hulls. Spot and displace through tubing pump in with
pump truck. 2 3/8" tubing @ 2071' circulated with cement w/104 sx.
with 2 1/2 sx. hulls. Squeezed 4 1/2" casing 15 sx. cement. Max.
pressure 600#. Shut in 600 P.S.I. Squeezed annulus to 600 P.S.I.
Shut in @ 600 P.S.I. No cement. 4 1/2" casing was perforated @ 1555'
by L.K. Wireline.

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1992
11-23-1992

Remarks: Cemented by: B.J. Services
Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES X ,CALC ,NO Dakota plug:YES X ,NO
Plugged through TUBING X , CASING . Elevation: GL

I did[X] / did not[] observe the plugging.

Marion J. Schmidt
(agent)

DATE 12-1-92

INV. NO. 36939