

15-051-22064-00-00
11-18

93
R

4-071018

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-22,064
SW NE SE /4 SEC. 29, 12 S, 20 W
1650 feet from S section line
990 feet from E section line

Operator license# 09346 Lease Ginther well # 2

Operator: Diehl Oil, Inc. County Ellis

Address: P.O. Box 234 Well total depth 3899 feet ^{126.72}
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Glenn D. Diehl Surface pipe 8 5/8 Inch @ 219 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services - Paul's Well Service License#

Address: Hays, Kansas 67601 - Ellis, Kansas 67637

Company to plug at: Hour: P.M. Day: 18 Month: November Year: 92

Plugging proposal received from: Glenn D. Diehl

Company: Diehl Oil, Inc. Phone: 913-625-6711

Were: 8 5/8" - 219' S.P. cwc w/150 sx. cement. 4 1/2" casing @ 3899'
w/150 sx. cement. 4 1/2" casing perforated @ 1450' cwc. w/300 sx. cement.
Perf's 3770' - 3788'. Proposal 275 sx. 65/35 pozmix - 8% gel. and 5 sx.
hulls. Pump in with pump truck. Load both 4 1/2" casing and 4 1/2" x
8 5/8" annulus from top to bottom. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:30P.M., Day: 18, Month: November, Year: 92

Actual plugging report: Diehl Oil Inc. ordered 275 sx. 65/35 pozmix -
8% gel. and 5 sx. hulls. Pumped in with pump truck. Pumped in 4 1/2"
casing with 15 sx. cement followed with 185 sx. cement with 3 1/2 sx.
hulls added. Max. pressure 900 P.S.I. Shut in @ 550 P.S.I.
Squeezed 4 1/2" x 8 5/8" annulus w/0 sx. cement. Max. Pressure 400
P.S.I. Shut in @ 400 P.S.I.

RECEIVED
STATE CORPORATION COMMISSION

11-23-1992
NOV 23 1992

Remarks: Cemented by: B.J. Services
Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES X, CALC , NO Dakota plug:YES X, NO
Plugged through TUBING X, CASING . Elevation: GL Division
Wichita, Kansas

I did[X] / did not[] observe the plugging.

Marion J. Schmidt
(agent)

INVOICED
DATE 12-1-92
WV. NO. 36938