

6 061964

API NUMBER 15-

SE, SEC. 29, T 12 S, R 20 WAE

990 feet from S section line

1650 feet from E section line

Lease Name Nicholson Well # 2

County Ellis 127.92

Well Total Depth 3936 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 7076

Operator: Black Diamond Oil Inc.

Name &

Address 1101 E 30th

Hays, Ks 67601

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Ivan Holt Well Service License Number

Address Russell, Ks. 67665

Company to plug at: Hour 10:30AM Day 2 Month: Oct Year: 19 89

Plugging proposal received from Kenneth Vehige

(company name) Black Diamond Oil Inc. (phone) 625-5891

Order 250 sks 65/35 poz 8% gel 5 sks bulls.

were:

Shot hole at 1565' & 600' Plugging Proposal Received by Gilbert G. Scheck

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:15PM Day: 2 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 250' w/200 sks. 4 1/2" set at

3840' w/100 sks. Top perf at 3788'. Ran tubing to 3835' and pumped 50 sks cement.

Pulled tubing to 1588' and circulated cement to surface. Pulled all tubing and filled

4 1/2" casing w/cement, Used ^{w/800 psi} 250 sks cement. 8 5/8" had been squeezed w/450 sks cement w/cement

to surface.

Remarks: By Allied.

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1989
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10-25-89

INV. NO. 26212

Signed Gilbert G. Scheck

(TECHNICIAN)

Gilbert G. Scheck