

To: 6041222
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-21,639

SE SE NE, SEC. 29, T 12 S, R 20 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6622

Lease Name Reitmayer Well # 1

Operator: Jason Oil

County Ellis 125,64

Name & Address Box 701

Well Total Depth 3866 feet

Russell, Ks. 67165

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258 w/165 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Ks

Company to plug at: Hour: 12:00 Day: 11 Month: September Year: 19 90

Plugging proposal received from Jim Schoenberger

(company name) JASON Oil (phone) _____

were: 4 1/2 casing set at 3866. w/200 sks cement: perfs at 3504. Perf anhy at 1553;

Shot casing at 2390. Recovered 960 of 4 1/2 casing. Ordered 250 sks 65/35 poz 8% gel w/

1/2 lb f.c. plus 5 sks hulls.

Marion J. Schmidt

Plugging Proposal Received by Dennis L. Hamel

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30PM Day: 11 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT _____ Casing parted at 960; pulled same: RIH w/tubing to 1550.

RIH w/perf strip gun, shot casing at anhy (1553) P.O.O.H. w/perf gun. Pumped 5 sks gel

followed w/25 sks cement disp w/2 sks gel. Pull up tubing to 950 (top of ^{csg} fish) pumped in tubing 200 sks 65/35 poz w/1/2 lb f.c. plus 400 lbs. hulls; cement circulated to surface,

P.O.O.H. w/tubing; filled 8 5/8 casing w/add 25 sks cement.

RECEIVED
STATE CORPORATION COMMISSION

10-3-1990
OCT 3 1990

Remarks: _____ (If additional description is necessary, use BACK of this form. CONSERVATION DIVISION Wichita, Kansas)

INVOICED

I (did) did not) observe this plugging.

DATE OCT 05 1990

Signed Dennis L. Hamel
(TECHNICIAN)

INV. NO. 29541

9-11
MAR 07 1991

Dennis Hamel