

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-00473-00-01  
Spot: NESENE Sec/Twnshp/Rge: 31-32S-6E  
3381 feet from S Section Line, 357 feet from E Section Line  
Lease Name: BARKMAN Well #: 1  
County: COWLEY Total Vertical Depth: 3130 feet

Operator License No.: 33405  
Op Name: ANSTINE & MUSGROVE INC.  
Address: PO BOX 391  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	172		300 TO SURFACE
PROD	5.5	3130		N/A

101.73

Well Type: SWD UIC Docket No: D25788.0 Date/Time to Plug: 09/02/2009 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Revd. from: KENNETH KIVETT Company: KIVETT WELL PLUGGING Phone: (620) 763-7740

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/03/2009 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

WHILE LAYING DOWN TBG AND PACKER OUT OF WELL, PACKER HUNG UP @ 1950'. WORKED PACKER LOOSE AND DROVE PACKER TO 2120'. CUT TBG @ 2109, LAYED DOWN TBG. RIH W/WIRELINE & SET CIBP @ 2105', DUMP BAILED 2 SXS CEMENT ON TOP. COMPLETED CELLER WORK. CEMENT @ SURFACE ON BACKSIDE OF 5-1/2" CASING. RIH W/TBG @ 360' CONSOLIDATED MIXED & PUMPED 95 SXS 60/40 POZMIS 4% GEL TO SURFACE. CEMENT CIRCULATED, PLUG DOWN 9-3-2009, 1:00 P.M. CONSOLIDATED CEMENT TICKET #23066. 9-4-2009, TOPPED WELL OFF BACK TO SURFACE W/25 SXS.

Perfs:

Top	Bot	Thru	Comments
3060	3068		CSG

INVOICED

DATE 11-17-09  
INV. NO. 2010060503


RECEIVED  
OCT 15 2009  
KCC WICHITA

Remarks: D-25,788

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)

