

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-19654-00-00
Spot: NE Sec/Twnshp/Rge: 6-34S-11E
3600 feet from S Section Line, 1980 feet from E Section Line
Lease Name: CASEMENT Well #: A 2
County: CHAUTAUQUA Total Vertical Depth: 1350 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A. OR PATRICIA R.
Address: 776 HWY 99
SEDAN, KS 67361

43.88

Well Type: EOR UIC Docket No: E21275.4 Date/Time to Plug: 09/03/2009 1:00 PM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S, INC. Phone:

Proposed Plugging Method: 50' plug at 1350', 50' plug at 700' and 350' to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/04/2009 10:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1350' gelled hole and spotted 2 sack plug. Pulled up to 700' and spotted 2 sack plug. Pulled up to 350' and tried to circulate cement to surface and couldn't. Pulled 1" out of casing. Came back next day and tagged cement at 200' with 1" and circulated cement to surface. A total of 29 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DISTRICT #3

OCT 8 2009 DAS

CHANUTE, KS

INVOICED
DATE 11-17-09
INV. NO. 2010060570


RECEIVED
OCT 16 2009
KCC WICHITA

Remarks: WELL WAS NEVER AUTHORIZED.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

