

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20483-00-00
Spot: S2 Sec/Twnshp/Rge: 26-29S-36W
1350 feet from S Section Line, 2620 feet from E Section Line
Lease Name: SMITH-TUNE UNIT Well #: 2
County: GRANT Total Vertical Depth: 2940 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	620		WITH 350 SX CMT
PROD	5.5	2939	732	WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/25/2009 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUG AT 2450' WITH 35 SX CMT & HULLS. PLUG AT 630' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.
95.55

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2009 1:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 250# HULLS & 35 SX CMT AT 2450'. TBG FISH @ 2485'. ROD FISH @ 2600'.
POOH W/ 5 1/2". RIH W/ 2 3/8" TBG TO 1200'. PUMPED 300# HULLS. POOH W/ 2 3/8"
TO 630'. PUMPED 50 SX CMT. 40 SX CMT AT 300'. 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
2773	2814	OH	

INVOICED
DATE 11-17-09
INV. NO. 2010060511

RECEIVED
OCT 15 2009

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

KCC WICHITA

District: 01

RECEIVED
OCT - 1 2009
KCC DODGE CITY

Signed Jack MacLuskey
(TECHNICIAN)

Form CR-273