

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20278-00-00  
Spot: S2SE Sec/Twnshp/Rge: 10-34S-39W  
660 feet from S Section Line, 1317 feet from E Section Line  
Lease Name: CARL MATZEN UNIT Well #: 1  
County: STEVENS Total Vertical Depth: 3113 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PKWY P  
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	600		WITH 300 SX CMT
PROD	5.5	3112	915	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2009 8:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (620) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

101.17

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE  
Date/Time Plugging Completed: 10/02/2009 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

RIH W/TBG TO 1400' & PUMP 25 SX CMT. PULLED TO 900' & PUMPED 500# HULLS, CIRCULATED HOLE WITH MUD, & 50 SX CMT. TAGGED PLUG @ 681'. PULLED TO 630' & PUMPED 70 SX CMT. PULLED TO 300' & PUMPED 40 SX CMT. PULLED TO 40' & PUMPED 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2967	3023	OH	

INVOICED

DATE 11-17-09

INV. NO. 2010060511

RECEIVED

OCT 15 2009

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed Steve Durrant  
(TECHNICIAN)

RECEIVED

OCT - 9 2009

KCC DODGE CITY