

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20988-00-01

Spot: NWSWNE

Sec/Twnshp/Rge: 4-32S-39W

1650 feet from N Section Line,

2310 feet from E Section Line

Lease Name: ISRAEL A

Well #: 6

County: MORTON

Total Vertical Depth: 6000 feet

Operator License No.: 5447

Op Name: OXY USA INC.

Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1723		WITH 675 SX CMT
COND	20	40		WITH 3.5 YDS CMT
DVT		3150		WITH 855 SX CMT
PROD	5.5	5999	0	WITH 615 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 09/18/2009 10:00 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: JOHN SCHOOLCRAFT

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed
Plugging
Method:

CIBP @ 5450' WITH 2 SX CMT OR 200#HULLS & 25 SX CMT. PLUG AT 1800' WITH 25 SX CMT. PLUG AT 600-0' WITH 75 SX CMT. CHECK BACKSIDE WITH 20 SX CMT.

195.00

Plugging Proposal Received By: KEN JEHLIK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/18/2009 2:30 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 600# HULLS. 1ST PLUG AT 2380' WITH 25 SX CMT. 2ND PLUG AT 1750' WITH 10 SX CMT. 3RD PLUG AT 550' TO 0' WITH 60 SX CMT. PRESSURED TO 500# & HELD. ANNULUS WAS FULL OF CMT. COULD NOT PUMP IN.

Perfs:

Top	Bot	Thru	Comments
5870	5880		
5850	5860		
5512	5524		

INVOICED

DATE 11-17-09

INV. NO. 2010060518

RECEIVED

OCT 15 2009

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED

SEP 25 2009

KCC DODGE CITY

Form CP-27