

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21122-00-00
Spot: SESE Sec/Twnshp/Rge: 33-31S-39W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: HOBBLE A Well #: 2
County: MORTON Total Vertical Depth: 6000 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1714		WITH 675 SX CMT
PROD	5.5	5999	0	WITH 1255 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/17/2009 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 5400' WITH 2 SX CMT. PLUG AT 1750' WITH 25 SX CMT. PLUG AT 600-0' WITH 75 SX CMT. CHECK BACKSIDE.

195.00

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2009 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

TOC @ SURFACE. PUMP 200# HULLS & 25 SX CMT AT 5463'. PLUG AT 1750' WITH 25 SX CMT. PLUG AT 600' WITH 64 SX CMT. CMT TO SURFACE. 5 1/2" X 8 5/8" ANNULUS FULL OF CMT. PRESSURED TO 350 PSI.

Perfs:

Top	Bot	Thru	Comments
5463	5465		

INVOICED
DATE 11-17-09
INV. NO. 2010060518

RECEIVED
OCT 15 2009
KCC WICHITA

Remarks: USED COMMON CMT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

OCT - 1 2009

KCC DODGE CITY

Form CP 2/3