

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00204-00-00
Spot: SE Sec/Twnshp/Rge: 27-23S-38W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: YATES Well #: 1
County: KEARNY Total Vertical Depth: 2668 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	315		WITH 175 SX CMT
L1	3.5	2084		120 SX W/ TENSION PKR
PROD	5.5	2667	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/10/2009 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PUMP 200# HULLS & 75 SX CMT. PERFORATE 3 1/2" X 5 1/2" @ 900'. PUMP 80 SX CMT OVER CAPACITY. PUMP 150 SX CMT DOWN 8 5/8" X 5 1/2". IF 3 1/2" DOES NOT TEST. WILL NEED PACKER
86.71

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2009 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG PUMPED 75 SX CMT & 150# HULLS TO 2100'. 2ND PLUG WAIT ON CMT 2.5 HOURS. TAG TOC @ 2048'. TESTED 3 1/2" TO 500#. PERFORATE 3 1/2" X 5 1/2" WITH 4 HOLES. ESTABLISH RATE. PUMPED 80 SX CMT WITH AN ESTIMATED 50 SX CMT OUT PERFORATIONS @ 600#. 3RD PLUG TESTED 5 1/2" X 3 1/2" ANNULUS TO 500#. 4TH PLUG PUMPED 30 SX CMT DOWN 8 5/8" X 5 1/2". SHUT IN PRESSURE 500#.

Perfs:

Top	Bot	Thru	Comments
2634	2650		
2586	2602		

INVOICED

DATE 11-17-09
INV. NO. 2010060527

RECEIVED
OCT 15 2009

Remarks: USED CLASS C CMT W/2% GEL BY ORR ENTERPRISES.

KCC WICHITA

Plugged through: CSG

District: 01

RECEIVED
SEP 30 2009

Signed

Ken Jehlik
(TECHNICIAN)

KCC DODGE CITY