

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19140-00-00
Spot: NWNENW Sec/Twnshp/Rge: 2-28S-4E
4635 feet from S Section Line, 3776 feet from E Section Line
Lease Name: AMBLER Well #: 4
County: BUTLER Total Vertical Depth: 2620 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2135		
SURF	8.625	60		SURFACE <u>85.15</u>
PROD	5.5	2610		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2009 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: JOE BURNETT Company: GRESSEL OIL FIELD SERVICE INC Phone: (620) 463-5161

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/28/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE AND SET CIBP @ 2,135', DUMP BAILED 3 SXS CEMENT ON TOP. PERFORATED SQUEEZE HOLES (5-HOLES) @ 250' -257', SWEDGED INTO 5-1/2" CASING, ESTABLISHED CIRCULATION, COPELAND ACID SERVICE MIXED & PUMPED 335 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 9/28/2009, 5:00 PM. COPELAND ACID SERVICE CEMENT TICKET # 34282. 9-29-2009, TAGGED CEMENT @ 125', INSIDE 5-1/2" & 50' OUTSIDE. RIH W/1" TBG @ 50', COPELAND ACID MIXED & PUMPED 12 SXS 60/40 POZMIX 4% GEL TO SURFACE, RIH W/1" TBG @ 125', COPELAND ACID SERVICE MIXED & PUMPED 12 SXS 60/40 POZMIX 4% GEL TO SURFACE. PLUG COMPLETE. CEMENT CIRCULATED. COPELAND ACID CEMENT TICKET #34283.

Perfs:


Top	Bot	Thru	Comments
2190	2200		
INVOICED DATE <u>11-17-09</u> INV. NO. <u>2010060504</u>			
RECEIVED OCT 15 2009 KCC WICHITA			

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)