

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Bowman Oil Company
Address: 805 Codell Road Codell, Kansas 67663
Phone: (785) 434-2286 M-F Operator License #: 6931
Type of Well: Oil Well (OWWO) DH KCCPKT Per CP 2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: September 24, 2009 (Date)
by: KCC District #4 Agent Pat Bedore (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3778' Bottom: 3781' T.D. original 3781'
Depth to Top: _____ Bottom: _____ (T.D. 3815')
Depth to Top: _____ Bottom: _____ (T.D. 6-24-09)

API Number: 15-163-21156-0001
Lease Name: Keller C SE (OWWO)
Well Number: #1 (Formerly Keller B #1)
Spot Location (QQQQ): _____ - SW - SW - SE
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 30 Twp. 10 S. R. 19 East West
County: Rooks County, Kansas
Date Well Completed: September 22, 2009
Plugging Commenced: September 24, 2009
Plugging Completed: September 24, 2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water & Oil	0	256'	8 5/8"	256'	0
		0	3780'	4 1/2"	3780'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Well was plugged According to KCC - District #4 - Hays, Kansas Instructions

tubing @ 3500', Spot 75 sacks of 60/40 Common/Poz with 200# hulls, pulled to 2428', spotted 75 sacks with 200# hulls, pulled to 1300', circulated cement with 75 sacks, pulled tubing, topped off with 15 sacks, Used 240 sacks 60/40 Common Poz Mix with 4% Gel.

See attached cementing ticket and card

Name of Plugging Contractor: Bowman Oil Co. A General Partnership License #: 6931
Address: P.O. Box 31 Russell, Kansas 67665
Name of Party Responsible for Plugging Fees: Bowman Oil Company
State of Kansas County, Rooks, ss.
Connie Jo Austin - Agent for Bowman Oil Company (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the

KCCPKT Per CP 2/3
RECEIVED
OCT 15 2009
KCC WICHITA

same are true and correct, so help me God.
NOTARY PUBLIC - State of Kansas

Jackie J. Langholz
My Appt. Expires 2-24-2013

(Signature) Connie Jo Austin
(Address) 805 Codell Road Codell, Kansas 67663

SUBSCRIBED and SWORN TO before me this 9th day of October, 2009
Jackie J. Langholz My Commission Expires: 2-24-09
Notary Public

Handwritten initials/signature



24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906
Voice: (785) 483-3887
Fax: (785) 483-5566

INVOICE

Invoice Number: 120068
Invoice Date: Sep 24, 2009
Page: 1

Bill To:
Bowman Oil Company 805 Codell RD Codell, KS 67663

Customer ID	Well Name# or Customer P.O.	Payment Terms	
Bowm	Keller C SE #1	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS2-03	Russell	Sep 24, 2009	10/24/09

Quantity	Item	Description	Unit Price	Amount
144.00	MAT	Class A Common	13.50	1,944.00
96.00	MAT	Pozmix	7.55	724.80
8.00	MAT	Gel	20.25	162.00
240.00	SER	Handling	2.25	540.00
50.00	SER	Mileage 240 sx @.10 per sk per mi	24.00	1,200.00
1.00	SER	Plug	875.00	875.00
50.00	SER	Pump Truck Mileage	7.00	350.00

ALL PRICES ARE NET, PAYABLE 30 DAYS FOLLOWING DATE OF INVOICE. 1 1/2% CHARGED THEREAFTER. IF ACCOUNT IS CURRENT, TAKE DISCOUNT OF

\$ 1448.95

ONLY IF PAID ON OR BEFORE

Oct 24, 2009

Subtotal	5,795.80
Sales Tax	307.18
Total Invoice Amount	6,102.98
Payment/Credit Applied	
TOTAL	6,102.98

\$ 4654.03

FRONTIER OIL COMPANY
1720 KSB&T BLDG
WICHITA, KS 67202

#1 KELLER "B"

30-10-19W
APPX SW SW SE

CONTR RED TIGER DRILLING CO CTY ROOKS

GEOL R. D. PARKER/J. A. ALBERTS FIELD MARCOTTE

E 2220 KB CM 9/16/80 CARD ISSUED 1/29/81 IP OIL WELL
TOP 3287-95
LKC 3498-3546 OA

API #
15-163-21156-00

API 15-163-21,156

SMP	TOPS	DEPTH	DATUM
ANH		1612	+ 608
BRNVLE LM		2925	- 705
TARK LM		3025	- 805
HOW		3181	- 961
TOP		3205	- 985
HEEB		3424	-1204
TOR		3448	-1228
LKC		3464	-1244
B KC		3673	-1453
CHTY CONG		3702	-1482
MARM		3725	-1505
SIMP		3757	-1537
ARB		3778	-1558
RTD		3781	-1561
NO LOG			

8-5/8" 256/170sx, 4 1/2" 3780/250sx

DST (1) 3216-3244 (TOP)/120-30-0-0,
REC 20' HOCM, 70' VSOCM, 60' WM
W/SPTS 0, ISIP 689#, IFP 57-102#

DST (2) 3320-3400 (TOP)/120-30-0-0,
REC 860' SL MSW, ISIP 1117#, IFP
79-520#

DST (3) 3418-3478 (HEEB, TOR)/60-30-0-0,
REC 15' M, ISIP 667#, IFP
57-57#

DST (4) 3474-3506 (LKC)/60-30-0-0, REC
45' M W/SCUM 0, ISIP 159#, IFP 45-
68#

+	+
+	+
+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

(OVER)

FRONTIER OIL COMPANY

CARD #2
#1 KELLER "B"

30-10-19W
APPX SW SW SE

500 G (15% REG), SWB PT LD & REC 2.32 BF, 20% O/1HR,
2.32 BF, 15% O/2ND HR, 1.74 BF, 15% O/3RD HR, PF (LKC)
4/3498-3504, SET 4 1/2" PLUG @ 3522, SWB DWN & REC 2.98 BF,
50% O, SWB 1.16 BF, 10% O, AC 500 G (15% REG), REC LD &
SWB 4.64 BF, 20% O/1HR, 4.06 BF, 30% O/2ND HR, 2.90 BF,
40% O/3RD HR, 2.90 BF, 40% O/4TH HR, PF (TOP) 4/3287-95,
SET 4 1/2" PLUG @ 3468, SWB DWN & REC 2.32 BW/30", SWB 4.64
BW/1HR, SET 2-3/8" T @ 3315, PF (TOP) 4/3234-40, TST WTR,
AC 500 G (15% REG), REC LD & SWB 4.06 BF, 40% O/1HR, 3.48
BF, 25% O/2ND HR, SWB AVER 1.74 BFPH, 15% O/6HRS, POP,
OIL WELL - PCTENTIAL NA

RECEIVED
OCT 15 2009
KCC WICHITA

