

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33392
Name: Keith F Walker Oil & Gas Co., LLC
Address 1: 103 West Boyd
Address 2: _____
City: Norman State: OK Zip: 73069 + _____
Contact Person: Steve Dixon
Phone: (405) 833-2994
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chester Depth to Top: 5586 Bottom: 5600 T.D. 5823
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 025-21148-00-01
Spot Description: _____
SWSW Sec. 31 Twp. 34 S. R. 22 East West
660 Feet from North / South Line of Section KCC
660 Feet from East / West Line of Section PKT
Footages Calculated from Nearest Outside Section Corner: PKT
 NE NW SE SW CP 2/3
County: Clark
Lease Name: Cobblestone Well #: 31-1R
Date Well Completed: 11-14-05
The plugging proposal was approved on: 9/14/2009 (Date)
by: Steve Durant (KCC District Agent's Name)
Plugging Commenced: 9/14/09
Plugging Completed: 9/16/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Chester</u>	<u>Gas</u>	<u>0-64</u>	<u>20</u>	<u>64</u>	<u>0</u>
		<u>0-732</u>	<u>8 5/8</u>	<u>732</u>	<u>0</u>
		<u>0-5823</u>	<u>4-1/2</u>	<u>5823</u>	<u>2309</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 40 bbls mud down 4-1/2. Set CIBP at 5533. Pumped 10 sacks of cement on plug. Shot 4-1/2 csg at 2309'. Layed down same. TIH with tbg. Pumped 50 sacks cement at 760'. TOH to 300'. Pumped 50 sacks cement. TOH to 60'. Pumped 20 sacks to surface

RECEIVED
OCT 15 2009
KCC WICHITA

Plugging Contractor License #: 33311 Name: Phil Dollar Oilfield Services, Inc.
Address 1: P.O. Box 744 Address 2: _____
City: Perryton State: TX Zip: 79070 + 0744
Phone: (806) 435-3373

Name of Party Responsible for Plugging Fees: Keith F. Walker Oil & Gas Co., LLC
State of OK County: Carter, ss. Alan Stacy
(Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Alan Stacy

PKT