

API NUMBER 15-051-23233-DD-DD

LEASE NAME FRIES

WELL NUMBER 1

13630 Ft. from S Section Line

2990 Ft. from E Section Line

SEC. 10 TWP. 12S RGE. 20 (E) or (W)

COUNTY ELLIS

Date Well Completed _____

Plugging Commenced 11-23-98

Plugging Completed 11-23-98

*Rec'd
 11-15-1998*

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Geist Oil Operations

ADDRESS 807 GRANT Victoria, Ks. 67671

PHONE (785) 735-2664 OPERATORS LICENSE NO. 30680

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 20, 1998 (date)

by Herb Dinges (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation Marmington Depth to Top 3833 Bottom 3845 T.D. 3945

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Tioga	oil	3424	3430	8 5/8	258'	0
Toronto	oil	3519	3522	4 1/2	3900'	0
Lansing	oil	3689	3693	4 1/2	3900'	0
Marmington	oil	3833	3845	4 1/2	3900'	0
Arb.	oil	3915	3920	4 1/2	3900'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Check back side

Name of Plugging Contractor Allied Cementing License No. N/A

Address P.O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geist Oil Operations

STATE OF KANSAS COUNTY OF ELLIS, ss.

Bill Geist

(Employee of Operator) or (Operator) o


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.


(Signature) Bill Geist

(Address) 807 GRANT Victoria, Ks. 67671

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 98

Sheila Kuhn
 Notary Public

My Commission Expires: 3-16-2002


 SHEILA KUHN
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Exp. 3-16-2002

11-23-1998

MIRU L+M Well serv. pulled Rods + Pump out. Latched on to Tbing + unset pkr. at 3200' come out w/ Tbing.

Run 2 $\frac{3}{8}$ Tbing in open ended to 3865'. Allied mix 40 SKS - 60-40 w 10% Jell w/ Halls, 300 lbs down Tbing.

Pulled up to 2920 a spot 15 SKS Jell. Pulled Tbing up to 1600' spot 25 SKS 60-40 cement. Pulled out of hole w/ Tbing + Tied on to 4 $\frac{1}{2}$ pumped 85 SKS - 60-40 w/ 10% Jell
~~at 800 psi. Shot in at 400 psi.~~

Tied on to 8 $\frac{7}{8}$ x 4 $\frac{1}{2}$ annulas a Press. up to 500 psi.
Unhooked + Finished Job @ 6:30 P.M. 11-23-1998.
STATE Rep. WAS ON LOCATION. Jay Pfeifer

