

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-23,823-00-00

LEASE NAME Morintzer

WELL NUMBER 1

SPOT LOCATION 2310' / FSL
1155' / FWL

SEC. 34 TWP. 12 RGE. 18 (X) or (W)

COUNTY Ellis

Date Well Completed 3-14-84

Plugging Commenced 8:30 A.M.

Plugging Completed 4:25 P.M.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Dreiling Ltd of Colorado

ADDRESS 410 - 17th St, Suite 1140, Denver, Co 80202

PHONE # (303) 623-6144 OPERATORS LICENSE NO. 5804

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	30' mud	3676	3706	8-5/8	217	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Hole was full of heavy mud. Pumped cement through drill pipe as follows 220 sacks total 50/50 pozmix 6% gel rat hole 10 sacks
1st cement plug at 3700' with 25 sacks mouse hole 10 sacks
2nd cement plug at 1400' with 25 sacks
3rd cement plug at 650' with 100 sacks with 1 sack flocele
4th cement plug at 225' with 40 sacks (see back)
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____
Address Hays, Kansas

STATE OF Colorado COUNTY OF Denver, ss.

Leslie Olson (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie Olson
(Address) 410 - 17th St., Suite 1140 Denver, Colorado 80202

RECEIVED
STATE CORPORATION COMMISSION
03-30-1984
MAR 30 1984
SUBSCRIBED AND SWORN TO before me this 27th day of March, 1984
CONSERVATION DIVISION
Wichita, Kansas

Notary Public
Herraine C. Murphy

My Commission expires: 9-2-87

Form CP-4 1-84
Revised 06-83

5th cement plug at 40' with 10 sacks on solid hull bridge and 8-5/8' wood and rubber plug.

