

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County. Sec. 10 Twp. 12 Rge. 20 (E) (W) W

Location as "NE/CNW/SW" or footage from lines SE SW NE
S. and C. Drig, Inc.

Lease Owner

Lease Name Richard Fries Well No. 1

Office Address 110 W. 8th Box 271 Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 10-7 19 64

Application for plugging filed 10-7 19 64

Application for plugging approved 10-7 19 64

Plugging commenced 10-7 19 64

Plugging completed 10-7 19 64

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4,000 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

242' of 8-5/8" surface casing. Cemented w/150 sks.
Filled hole with heavy mud to 600'. Set plug. Mixed & poured 20 sks.
through drill pipe. Filled w/heavy mud to 180'. Set plug. Mixed &
poured 20 sks. through drill pipe. Filled hole to 40'. Set plug.
Added 1/2 sack hulls & 10 sks cement. Plugging completed at 11:45 p.m.
10-7-64.

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1965
01-13-1965
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Co. Inc. (If additional description is necessary, use BACK of this sheet)
Address

STATE OF COUNTY OF ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Sullivan

Box 271 Hays, Kas.
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 1965

My commission expires March 26, 1968

Notary Public.



15-051-19257-00-00

CERTIFIED DRILLER'S LOG

COMPANY: S. and C. Drlg, Inc.
CONTRACTOR: S. and C. Drlg, Inc.
COMMENCED UNDER SURFACE: 9-24-64
COMPLETED: 10-7-64
ELEVATION: 2242' Gr. Level
POTENTIAL: D & A

LEASE: Richard Fries
LOCATION: SE SW NE 10-12-20W
Ellis County
CASING RECORD: 242' of 8-5/8"
Cemented with 150 sacks.

FIGURES DENOTE BOTTOM OF FORMATION. THESE ARE K.B. MEASUREMENTS.
(Gr. level plus 5')

<u>FORMATION:</u>	<u>DEPTH:</u>
Surface clay & Ft. Hays lime	50
Sand & Shale	82
Shale & Shells	210
Shale	465
Shale & Shells	1125
Shale & Sand	1325
Red Bed	1653
Anhydrite	1689
Shale	1915
Shale & Shells	2101
Shale	2225
Shale & Lime	2445
Shale & lime streaks	2645
Lime	2800
Lime & Shale	3624
Lime	3868
Conglomerate	3930
Arbuckle	4000

T.D.

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1965
01-13-1965
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the
above log to the best of my knowledge.

S. and C. Drilling, Inc.

S & C Drilling Inc.
D. J. Sullivan
By: D. J. Sullivan, Exec.-Vice Pres.