

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Nadel and Gussman, LLC
Address: 15 E. 5th St. Ste. 3200 Tulsa OK 74103
Phone: (918) 583-3333 Operator License #: 32638
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-6-08 (Date)
by: Mike Meier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-10033-0000
Lease Name: Dreyer
Well Number: 1-4
Spot Location (QQQQ): _____ C-SW
1320 Feet from North South Section Line
4013
1320 Feet from East West Section Line
Sec. 4 Twp. 32 S. R. 43 East West
County: Morton
Date Well Completed: 1-5-55
Plugging Commenced: 10-6-08
Plugging Completed: 10-7-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	625	—
				5 1/2	3360	—
			stuck	2 7/8	3312	2193

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2 7/8 was stuck. Mixed 50 lb. hulls & 17 sx cmt to plug bottom of 2 7/8 from 3312 to 2700. Shot 2 7/8 loose @ 2193. Circ hole w/mud & mixed 25 sx plug in 5 1/2 from 2193 to 1993, mixed 50 sx 650 to 250, 5 sx 40 to 0 annulus was cmt. Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON-PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Nadel and Gussman, LLC

RECEIVED
SEP 03 2009

State of Oklahoma County, Tulsa, ss.


KCC WICHITA

David Yaeger, Chief Reservoir Engineer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) David W Yaeger
(Address) 15 E. 5th St., Ste 3200, Tulsa, OK 74103

SUBSCRIBED and SWORN TO before me this 1 day of _____

Kathy Garraw
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials/signature

RECEIVED
SEP 03 2009
KCC WICHITA

Attn
John M.

SARGENT A. J HORTON
PLUGGING, INC.
Route 1, Box 49BA
Tyrone, OK 73951-9731

No 4400

DAILY REPORT

DATE 10-7-08 FROM 700 TO 500

COMPANY Nadel & Gussman FARM NO. Dreyer 1-4

HOURS WORKED	NAME
10	JS
10	JC
10	TJ

CONTRACTOR'S TIME _____ COMPANY'S TIME 8 @ 200
2 @ 110

REMARKS: Shot 2 7/8 loose @ 2193.

Circ. hole w/mud & mixed 25 sx
stub plug from 2193 to 1993. Pulled
2 7/8 to 650. Mixed 50 sx 650 to 250.
Pulled to 40. Mixed 5 sx 40 to 0.
Tore down pole & pump truck, will
cut 8 5/8 + 5 1/2 + cap 8 5/8 3 ft. below
G.L. 10-8.

cost 3440
+ mud

True Value

ELKHART LUMBER COMPANY, INC.

West Stateline Road • HC1 Box 94
Elkhart, Kansas 67950
620-697-4515

LOADED BY	DELIVERED BY	TIME IN
CHECKED BY	HOW DELIVERED	TIME OUT

10/06/08 15:08 01

INVOICE

NO. 2507198

NADEL AND GUSSMAN
BOX 773
ELKHART, KS

67950

MISC: DREYER 1-4

P	405
A	1
W	1
D	1

CUST#: 10910.0000 DEL DATE: 10/06/08
918-583-3333

TERMS: NET 10TH

✓	L#	QUANTITY	DESCRIPTION	ITEM #	UNITS	PRICE/UNIT	AMOUNT
		90	PORTLAND CEMENT TYPE 1 94#	78011050A	90	10.50 EA	945.00
	2D	1	COTTONSEED HULLS	11800200A	1	12.99 EA	12.99

True Value

COPY

John

	SUBTOTAL	957.99
D	DELIVERY CHARGES	121.50
D	CITY/STATE S/TA	68.01
	TOTAL	1147.50

THANK YOU FOR YOUR PATRONAGE.
TERMS: Net 10th of the Month. FINANCE CHARGE of 1 1/2% per month will be added to all past due balances. This is an ANNUAL PERCENTAGE RATE of 18%. The Minimum Finance Charge is \$1.00 per Month.

Received

By

X *[Signature]*

RECEIVED
SEP 03 2009
KCC WICHITA