

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hartman Oil Co., Inc.
Address: 10500 E. Berkeley Square Parkway, Suite 100
Phone: (620) 277-2511 Operator License #: 30535
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 6/13/08 as per Steve Durant (Date)
by: Witness by Ken Jehliik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Morrow Depth to Top: 4746' Bottom: 4758' T.D. 4818'
Pawnee Depth to Top: 4456' Bottom: 4462' T.D. 4818'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 055-10061-00-00
Lease Name: Garry
Well Number: #2
Spot Location (QQQQ): _____ - NW - NW - NW
330' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 4 Twp. 23 S. R. 33 East West
County: Finney
Date Well Completed: 11/23/62
Plugging Commenced: 8/27/09
Plugging Completed: 8/27/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		375"	surface	8 5/8"	375'	none
		4870'	production	4 1/2"	4870'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

As per KCC - Set CIBP @ 4450' w/2 sks cmt - Set 2nd CIBP @ 1150' - PSI test CSG to 800# - Perforated 4 holes @ 1100' - Mix 230 sks 60-40 poz w/ 4% Gel & Pump down 4 1/2" CSG @ 600# - Mix 65 sks 60-40 poz w/4% Gel & Pump down backside - Shut in @ 200#.

Name of Plugging Contractor: Allied cement Co. & Hartman Oil Co., Inc. License #: 30535
Address: 10500 E. Berkeley Square Parkway, Suite 100
Name of Party Responsible for Plugging Fees: Hartman Oil Co., Inc.
State of Kansas County, Finney, ss.
S T Mitchell
KCC CP213
99996 RECEIVED
SEP 11 2009
KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) S.T. Mitchell
(Address) 3545 W Jones Ave. Garden City, KS 67846

SUBSCRIBED and SWORN TO before me this 10th day of September, 2009
Mary L Riffel My Commission Expires: 1-13-2010
Notary Public



MARY L. RIFFEL
KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DATE 8/27/09 TIME 5:30 AM/PM (M)

OPERATOR Hartman Oil Co

OPERATOR LICENSE NO. 30535 API# 15- 055-10061-00-00

PLUGGING CONT. Allied Cementing LICENSE NO. _____

PUSHER Brian Meyer WITH Hartman Oil

LEASE NAME & WELL NO. Garry #2

LEGAL 330 FNL & 330 FWL NW/4 NW/4 Sec 4-23-33rd COUNTY Finney

GPS: Latitude 38.09006°N Longitude 100.95525°W

TD 4870 PBTD _____ CP None S.P. 8 5/8" @ 375' w/ 275' sx

OTHER CASING 4 1/2" @ 4870' WI ? SX CMT _____
TOC by bond log is 3100'

PERFORATED AT 4746'-4758' & 4456'-4462'

LINER FROM None TO _____ WI _____ SX CMT _____

MARKER DEPTH Stone Corral 1 1/2 @ 1880' ±, Permian Top @ 1075'

BOTTOM PLUG CIBP @ 4400' w/ 2' sx cmt by Halliburton

CASING RECOVERY None

TOP PLUG(S) CIBP @ 1110' by Halliburton

Allied tested esg to 800# holding. Perf 4 holes @ 1060'

Allied took injection rate 1 1/2 BPM @ 750 psi w/ water.

Pump 80' sx cmt, 200# balls @ 135' sx cmt at 900# increasing to 700#.

No blow or circulation up annulus.

Pump 65' sx cmt down 4 1/2" x 8 5/8" annulus @ 150 psi holding.

Top off 4 1/2" esg w/ 15' sx. Plugging Complete.

STARTING TIME 12:00 PM COMPLETION TIME 5:30 PM

RECEIVED
SEP 11 2009

TYPE OF CEMENT & CEMENTER 60/40 Pac 470gel Allied

KCC WICHITA

PLUGGED THROUGH: (C) CASING TUBING DRILL PIPE (CIRCLE ONE)

PLUGGING ORDERS GIVEN BY Kencelkik PLUGGING WITNESSED BY Kencelkik