

6 050234

15-195-21786-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195 21 786
S 8 NE NE, SEC. 5, T 12 S, R 21 W 10

4290 feet from S section line
330 feet from E section line

Lease Name Armbruster Well # 1

County Trego 133.25

Well Total Depth 4100 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250 ✓

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Operator Name & Address Energy Exploration Inc
10020 South Broadway
Wichita Kansas 67211

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Co. License Number 5422

Address 801 Union Center, Wichita, Kas. 67202

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Wilmer Drilling

(company name) Abercrombie Drilling Co. (phone) _____

Work: Order 225 sup 60/40 9oz mix 6% Gel 3% CC. 1 sac flocc 8 5/8 Plug
1 sac hulls. Circulate hole with heavy mud, with heavy mud
between all plugs - good circulation and no fluid loss.

1st Plug in 1st - 2nd plug 1st - 3rd plug @ 1000' - 4th plug 280' w/ 40 sup
5th Plug 40' w/ 8 5/8 plug 1 sac hulls and 10 sup - 15 sup in rat hole.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:15 PM Day: 4 Month: Oct Year: 1985

ACTUAL PLUGGING REPORT

1st Plug @ 4051' w/ 25 sup 15 sup in rat hole

2nd Plug @ 1834' w/ 25 sup

* 3rd Plug @ 1212' w/ 110 sup 1 sac flocc Cemented by B.J. Titon

4th Plug @ 290' w/ 40 sup

5th Plug @ 40' w/ 8 5/8 plug 1 sac hulls + 10 sup

Remarks: 3rd Plug order were changed from my order of 1000' to 1212'
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
OCT 15 1985

INVOICED

Signed Gilbert P. Leiker (TECHNICIAN)

41
10-11-85
mm

CONSERVATION DIVISION

INV. NO. 10644 NOV 13 1985

FORM CP-2/3 Rev. 01-84